BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

BBMP/2019-20/EL/WORK_INDENT36111

Arranging power supply to an extent of 600KVA Under HT Installation for Sewage treatment plant in favour of M/s BEL. Thindlu Yelahanka Bangaluru-97 in O and M 22A C9 Sub division Under SELF EXECUTION.

SNo	Quantity	Item Name	Unit	Rates quoted by Sri.MADHUSUDHAN A N (SURAKSHA ELECTRICALS)	
				In figures	In words
1	1.00	Supplaying of 4 Way RMU, 2OD + 2VL (One Incomer + TWo Breakers + One Outgoing) with DAS Specification as per BESCOM Specification	No	934752.00	Rupees Nine Lakh(s) Thirty Four Thousand Seven Hundred Fifty Two Only
2	4.00	Supplaying of Spun pole 11.0 mtr long as per BESCOM Specification	No	18872.00	Rupees Eighteen Thousand Eight Hundred Seventy Two Only
3	6.00	Supplaying of H Frame set for 11KV 400A Double break GOS mounting as per BESCOM Specification	SET	4170.88	Rupees Four Thousand One Hundred Seventy And Paise Eighty Eight Only
4	6.00	Supplaying of 11kV G.O.S 400A Double break as per BESCOM Specification	Set	19650.40	Rupees Nineteen Thousand Six Hundred Fifty And Paise Forty Only
5	6.00	Supplaying of Earthing materials as per BESCOM Specification	No.	1681.12	Rupees One Thousand Six Hundred Eighty One And Paise Twelve Only
6	1.00	Erection of 4 Way RMU, 2OD + 2VL (One Incomer + TWo Breakers + One Outgoing) with DAS Specification as per BESCOM Specification	No	5568.64	Rupees Five Thousand Five Hundred Sixty Eight And Paise Sixty Four Only
7	4.00	Erection of Supplaying of Spun pole 11.0 mtr long as per BESCOM Specification	No	1848.00	Rupees One Thousand Eight Hundred Forty Eight Only
8	6.00	Erection ofH Frame set for 11KV 400A Double break GOS mounting as per BESCOM Specification	SET	235.20	Rupees Two Hundred Thirty Five And Paise Twenty Only
9	6.00	Erection of11kV G.O.S 400A Double break as per BESCOM Specification	Set	712.32	Rupees Seven Hundred Twelve And Paise Thirty Two Only
10	6.00	Erection of Earthing materials as per BESCOM Specification	No.	567.84	Rupees Five Hundred Sixty Seven And Paise Eighty Four Only
11	6.00	Digging of pit for providing GI pipe type earthing	Per pit	563.36	Rupees Five Hundred Sixty Three And Paise Thirty Six Only
12	4.00	Pole Base 11mt spun pole concreting	Each	817.60	Rupees Eight Hundred Seventeen And Paise Sixty Only
13	1.00	Supplaying of Load Break Switch 11 KV class as per BESCOM Specification	Nos	63436.80	Rupees Sixty Three Thousand Four Hundred Thirty Six And Paise Eighty Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

	Quantity	Item Name	Unit	Rates quoted by Sri.MADHUSUDHAN A N (SURAKSHA ELECTRICALS)	
				In figures	In words
14	2.00	Construction of plat form (1.5x1.5x1.2) mtr in size stone, for erection of transformers/ Heavy equipment including all materials,labour as per BESCOM Specification	Each	29569.12	Rupees Twenty Nine Thousand Five Hundred Sixty Nine And Paise Twelve Only
15	3.00	Supplaying of Earthing materials as per BESCOM Specification	No.	1681.12	Rupees One Thousand Six Hundred Eighty One And Paise Twelve Only
16	8.00	Supplaying of Straight through jointing kit 3X95 Sq mm as per BESCOM Specification	No.	7258.72	Rupees Seven Thousand Two Hundred Fifty Eight And Paise Seventy Two Only
17	5.00	Supplaying of Cable termination kit 3X95 Sq mm XLPE indoor as per BESCOM Specification	set	3717.28	Rupees Three Thousand Seven Hundred Seventeen And Paise Twenty Eight Only
18	5.00	Supplaying of Cable termination kit 3X95 Sq mm XLPE outdoor as per BESCOM Specification	set	4037.60	Rupees Four Thousand Thirty Seven And Paise Sixty Only
19	12.00	Supplaying of GI Pipe 100mm Dia for drain crossing, cable rising etc	mtr	1391.04	Rupees One Thousand Three Hundred Ninety One And Paise Four Only
20	90.00	Supplaying of River Sand	cmt	1904.00	Rupees One Thousand Nine Hundred Four Only
21	12.00	Supplaying of Cable Covering Tiles 125x125x40 mm	Each	5600.00	Rupees Five Thousand Six Hundred Only
22	1125.00	Cable trench excavation (0.75x1.0x1.5KM CABLE LENGHT)	Cmt	253.12	Rupees Two Hundred Fifty Three And Paise Twelve Only
23	45.00	Supplaying of RCC Hume pipe 2000mm long, 150mm dia	No.	336.00	Rupees Three Hundred Thirty Six Only
24	45.00	Supplaying of Collars for RCC Hume pipe	No.	89.60	Rupees Eighty Nine And Paise Sixty Only
25	30.00	Supplaying of Route and Joint indicating stones	No.	145.60	Rupees One Hundred Forty Five And Paise Sixty Only
26	1.00	Erection of Load Break Switch 11 KV class as per BESCOM Specification	Nos	2327.36	Rupees Two Thousand Three Hundred Twenty Seven And Paise Thirty Six Only
27	1.00	Erection of 11kV HT Metering cubicle of different CT Ratio, Both side cable entry type with 3CT & 3PTs, With Transparent Cover TTB, with 30x8mm Cu Bus bars, Modem and 2 Nos of Meters for 3Ph 4 Wire Metering without Load Break Switch (HT Metering Box Fabricated out of 3mm MS Sheet duly epoxy powder coated) as per revised Specification as per BESCOM Specification	Nos	1527.68	Rupees One Thousand Five Hundred Twenty Seven And Paise Sixty Eight Only
28	3.00	Erection of Earthing materials as per BESCOM Specification	No.	563.36	Rupees Five Hundred Sixty Three And Paise Thirty Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-64

31/x/19

	Quantity	Item Name	Unit	Rates quoted by Sri.MADHUSUDHAN A N (SURAKSHA ELECTRICALS)	
				In figures	In words
29	8.00	Erection of Straight through jointing kit 3X95 Sq mm as per BESCOM Specification	No.	2088.80	Rupees Two Thousand Eighty Eight And Paise Eighty Only
30	5.00	Erection of Cable termination kit 3X95 Sq mm XLPE indoor as per BESCOM Specification	set	1914.08	Rupees One Thousand Nine Hundred Fourteen And Paise Eight Only
31	5.00	Erection of Cable termination kit 3X95 Sq mm XLPE outdoor as per BESCOM Specification	set	1914.08	Rupees One Thousand Nine Hundred Fourteen And Paise Eight Only
32	12.00	Erection of GI Pipe 100mm Dia for drain crossing, cable rising etc	mtr	56.00	Rupees Fifty Six Only
33	90.00	Spredding of River Sand	cmt	187.80	Rupees One Hundred Eighty Seven And Paise Eighty Only
34	12.00	laying of Cable Covering Tiles 125x125x40 mm	Each	3206.56	Rupees Three Thousand Two Hundred Six And Paise Fifty Six Only
35	45.00	laying of RCC Hume pipe 2000mm long, 150mm dia	No.	49.28	Rupees Forty Nine And Paise Twenty Eight Only
36	30.00	Erection of Route and Joint indicating stones	No.	84.00	Rupees Eighty Four Only
37	825.00	Refilling and consolidation	Cmt	56.00	Rupees Fifty Six Only
38	3000.00	HT Cable GROUP A: Supplying and laying of high tension 11KV cable, Dry Curing & Dry Cooling with true triple extrusion, simultaneously through a single common head, 3 core under ground XLPE (E) cable having stranded compact circular aluminium conductor, screened insulated, insulation screened with extruded semiconducting compound in combination with copper tape, core laid up extruded inner sheathed of GI flat strip armoured and overall PVC sheathed with specified IS 7098/11/85 with latest amendments & confirming to the GTP of GROUP-A 3Cx95sqmm	mtr	1164.80	Rupees One Thousand One Hundred Sixty Four And Paise Eighty Only

Executive Engineer 31/X/19
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Contractor

Executive Engineer
Project Division
Yelahanka Zone